

July 17, 2008

Attention all bidders

Re: Brunswick County Department of Social Services Building, Kitchen Expansion,
Addendum #6

The following clarifications, additions, deletions, revisions, and / or modifications are hereby made a part of the Construction Documents and thus change the original documents only to the extent hereby stated.

1. **BID PACKAGE 2B:**

- a) Bid length for auger cast piles shall be 60'-0".
- b) Tops of pile caps and grade beams shall be 2'-0" below finish floor.
- c) Temporary building pad elevation at start of auger cast pile installation shall be 1'-8" below finish floor or 1'-0" below final building pad elevation.
- d) Pile capacity shall be 30 tons.

If you have any questions or comments, please feel free to call.

Frank Randel
Project Architect